





# BOUNDARY SURVEY





## **SURVEYOR'S NOTES:**

1— The above captioned Property was surveyed and described based on the above Legal Description: Provided by Client.

NOT TO SCALE

2— This Certification is only for the lands as described. It is not a certification of Title, Zoning, Easements, or Freedom of Encumbrances.

3— There may be additional Restrictions not shown on this survey that may be found in the Public Records of this County, Examination of ABŠTRACT OF TITLE will have to be made to determine recorded instruments, if any affecting this property.

The expected use of the land, as classified in the Standards of Practice (5J—17 FAC), is "Residential High Risk". The minimum relative distance accuracy for this type of boundary survey is 1 foot in 10,000 feet. The accuracy obtained by measurement and calculation of a closed geometric figure was found to exceed this requirement.

5— Foundations and/or footings that may cross beyond the boundary lines of the parcel herein described are not shown hereon.

6— Not valid without the signature and the original raised seal of a Florida Licensed Surveyor and Mapper. Additions or deletions to survey maps or reports by other than the signing party or parties are prohibited without written consent of the signing party or parties.

7— Contact the appropriate authority prior to any design work on the

herein—described parcel for Building and Zoning information. 8— Underground utilities are not depicted hereon, contact the appropriate authority prior to any design work or construction on the property herein described. Surveyor shall be notified as to any deviation from utilities shown

9— The surveyor does not determine fence and/or wall ownership.

10-Ownership subjects to OPINION OF TITLE. 11-Type of Survey: BOUNDARY SURVEY.

12—The North arrow and bearings shown hereon based on recorded plat of "MARRIOTT SPRINGHILL SUITES", according to the plat thereof, as recorded in

Plat Book 161, Page 32, of the Public Records of Miami-Dade County, Florida. 13—All measurements shown hereon are made in accordance with the United States Standard Feet.

14—Flood Zone Data: Community/ Panel #120637/0144/L Dated:9/11/09

Flood Zone: "AE" Base Flood Elevation = +8.0' 15—Elevations shown, if any, hereon are relative to National Geodetic Vertical Datum (1929 Mean Sea Level).

16—Benchmark Used: Miami—Dade County Benchmark #H-396. Elevation = +13.2317—This BOUNDARY SURVEY has been prepared for the exclusive use of the entities named hereon. The Certificate does not extend to any <u>unnamed party:</u>

I HEREBY CERTIFY THAT: in the professional opinion of the undersigned Professional Surveyor and Mapper in the State of Florida, the following Boundary Survey meets the requirements of the Standards of Practice as set forth by the Florida Board of Professional Surveyors and Mappers in Chapter 5J-17, Florida Administrative Code, pursuant to Section 472.027, Florida Statutes. Further, this certificate is based on observations of field measurements performed on 09/24/2016 and other information available to the undersigned at the time the services were rendered.

Copies of this Boundary Survey are not valid without the seal and the original raised seal of a Florida licensed surveyor and mapper, said embossed copies are for the specific use of those entities that the Boundary Survey have been certified to.

> Professional Surveyor & Mapper State of Florida Reg. No.5880

### LEGEND

—— он —— Overhead Wire Line —— // —— // —— Wood Fence 

—--—-- Monument Line BRG=Bearing CH=Chord ∆=Delta

=Conc. Pole 🜣 =Light Pole =Fire Hydrant ₩V =Water Valve TV = Cable Tv Box L=Length R=Radius T=Tangent (M) =Manhole

=Existing Elevations A/C=Air Conditioner Conc. =Concrete Catch Basin C.B.S. =Concrete Block & Stucco ◆ Water Meter D.E. =Drainage Easement D.M.E.=Drainage Maintenance Easement F.D.H. =Found Drill Hole S =Sanitary Manhole F.F.E. =Finish Floor Elevation F.I.P. =Found Iron Pipe/Pin ◯ =Wood Pole F.I.R. =Found Iron Rebar

F.N. =Found Nail F.N&D =Found Nail & Disc F.P.L. =Florida Power Light Transformer L.M.E. =Lake Maintenance Easement (M) = MeasuredP.O.B. =Point of Beginning

EM = Electric Meter Box P.O.C. = Point of Commencement  $\square$  =Traffic Signal Box (R) =Record Res. =Residence ≥ =Monitoring Valve SIP/R =Set Iron Pin/Rebar S =Spread U.E. =Utility Easement

#### PROPERTY ADDRESS:

15800 NW 77 COURT, MIAMI LAKES, FLORIDA 33016 FOLIO No.: 32-2015-044-0010

#### **LEGAL DESCRIPTION:**

Tract "A" of "MARRIOTT SPRINGHILL SUITES", according to the plat thereof, as recorded in Plat Book 161, Page 32, of the Public Records of Miami-Dade County, Florida.

SURVEYOR'S CERTIFICATE:

DRAWN: J.G. CHECKED: P.J.A. SCALE: 1" = 30'

FIELD DATE: 09/22/2010 JOB NUMBER: RP16-082

0

SHEET:

OF 1 SHEET